# BRUHATH BENGALURU MAHANAGARA PALIKE

## Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

## APPROVED TENDER SCHEDULE –'B'

Item No: 45

Name of Work:- Maintenance of footpaths, replacement of damaged covering slabs, kerbs and other emergency works in ward no:03 of Yelahaka Satellite Town Sub Division

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved RatesSri Manjunatha Y G | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16 | Cum | 62.00 | 270.00 | Rupees two hundred seventy only |
| 2 | KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2015-16) | Cum | 62.40 | 70.00 | Rupees seventy only |
| 3 | KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2015-16) | Cum | 16.92 | 5000.00 | Rupees five thousand only |
| 4 | KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2015-16,p.no13,sno4.11) | sqm | 40.08 | 6000.00 | Rupees six thousand only |

| | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved RatesSri Manjunatha Y G | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 5 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2015-16,p.no17,s.no4.46) | Qit. | 40.08 | 6800.00 | Rupees six thousand eight hundred only |
| 6 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2 (pwd sr2015-16, p.no15/4.31) | sqm | 216.00 | 300.00 | Rupees three hundred only |
| 7 | Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate). | sqm | 37.80 | 1450.00 | Rupees one thousand four hundred fifty only |
| 8 | Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete.(pwd sr 2015-16,.n o25 5.30) | Nos | 100.00 | 300.00 | Rupees three hundred only |
| 9 | JCB Excavator With operator (BCSR 14-15 Page noXXXXVI Code 1031) | days | 15.00 | 6500.00 | Rupees six thousand five hundred only |
| 10 | KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness ) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No 101, I.No 14.6) | sqm | 108.00 | 899.50 | Rupees eight hundred ninety nine and paise fifty only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.